

Moray West Landfalls Pipe-Pushing in Scotland Challenges and Solutions

27th DCA Annual Congress Jez Seamans LMR Drilling Leipzig 6th October 2023



Contents

- Project Introduction
- **2** Ground Conditions
- 3 Engineering
- 4 Drilling Works
- 5 Duct Installation
- 6 Summary




DCA



1 Project Introduction


Project Details

- Client Ocean Winds (50% EDPR & 50% ENGIE)
- Offshore Cable Contractor Nexans Norway
- Onshore Cable Contractor Nexans France
- 2 no. 65km HVDC export cables transmit power to shore
- From landfalls HVDC cables run to Convertor
 Station and Electrical Substation 20km from
 landfall site

















Project Introduction

Landfall Details

- 30m high coastal cliffs
- 2 no. drills required
- Minimum duct ID of 450 mm
- Drill length to be minimised
- Depth of cover to be minimised
- Several potential sites to the east of Sandend
- Geology (as always) critical






1 Project Introduction

Landfall Details

- 6 possible sites
- Client's Preferred options :
 - Broad Craig
 - Redhythe
- LMR's preference:
 - Broad Craig:
 - Shorter
 - Exit closer to
 - offshore boreholes








2 Ground Conditions

Site Investigation

- BGS Data
- 2 no. onshore boreholes
- 2 no. offshore boreholes
- Onshore and offshore geophysical survey data








2 Ground Conditions

Site Investigation – Boreholes & Geophysics

- Boreholes aligned with BGS Date
- 5m of sand and gravel overlying quartzite at entry points
- Quartzite and Psammite for most of drills
- Gravel and sands approaching exit points
- Overburden thicker offshore








2 Ground Conditions

Site Investigation – Rock Characteristics

- Boreholes described
 very strong rocks of
 Redhythe Quartzite
 Formation
- Lab tests indicated 25-100 MPa
- Highly/extremely
 abrasive
- Challenging but drillable





BH4 - UCS Tests

O BH5 - UCS Tests

BH5 - Point Load Tests

 \circ

Rock Strenth (MPa x 1 for UCS tests, MPa x 10 for Point Load Tests)

90 100 110 120 130 140 150

70 80

50 60


10 20 30 40



2 Ground Conditions

Site Investigation – Approaching Exit

- Geophysical Data showed 2-3 m of sediment above bedrock at exit points
- Potential 0.5m layer of gravel
- Mostly sand above this gravel layer
- Sediments much thicker offshore





3 Engineering Drill Profiles


DCA

Move Exit Point Inshore slightly – less overburden and closer to borehole

Increase Drill Radius to 750m (1,000 x hole dia.)

Straight tangent to allow casing installation

To incorporate these criteria required moving entry points inland








3 Engineering

Drill Alignments

Move exit points to west to:

- Move closer to boreholes
- Reduce depth of overburden


To incorporate these criteria required reducing exit point water depth from 10m LAT to 9.5m LAT at western exit point







Drilling Contractors Association (DCA-Europe) Dogger Bank A & B Offshore Wind Farm





- The Vector gyro system was used with Inrock providing the tooling and survey services. Features of system included:
 - Gyro data avoiding corruption from magnetic interference. Essential with large drilling assemblies and tight tolerances
 - 150m entry coil for integrated Paratrack system allowed verification of elevation and inclination bias
 - PWD system provided real-time annular pressure data
 - Ability to house the steering tool in any size of drill collar with any form of connection
 - No 'HDD-world' limit on operating pressure of gyro flexibility with mud motor specification





Drilling Contractors Association (DCA-Europe) Bank A & B Offshore Wind Farm

3 Engineering

Duct Design

- Design Assessment determined need for SDR11 duct specification
- 560mm SDR 11 PE100 duct specification chosen to provide minimum 450mm ID
- Duct to be welded inland from drill site and to be pushed into the hole using a pipe pusher
- Duct to be internally debeaded
- Integrity verification to include :
 - Weld Records
 - Video of debeaded joints
 - Air-test pre-installation
 - Gauging-pig run post-installation





Drilling Contractors Association (DCA-Europe) Bank A & B Offshore Wind Farm

3 Engineering

Duct Termination Design

- Pushing duct means offshore end of duct passes through hole.
- Ducts tend to require a fitting on the seaward end to :
 - Allow the end to be sealed securely while awaiting cable installation, often a year or more later.
 - For the fitting of a bellmouth prior to cable installation.
 - Allow a cable seal to be fitted post-cable installation to enable annular grouting
- Conventional solutions include:
 - Fitting a mechanical coupler to the end of the pipe on the seabed.
 - Push through excess pipe, lift duct-end to a vessel and fit/weld a fitting to the end of the duct before lowering back to the seabed and potentially pulling the duct back up the hole into the preferred position.
- Solution needs to provide an internally flush surface for the cable.
- An alternative solution accepted by the Client on this Project and worked well.





Drilling Contractors Association (DCA-Europe) Dogger Bank A & B Offshore Wind Farm

3 Engineering

Duct Termination Design

• This involved a tapered end-section of the duct which allowed a welded flange to be fitted to the duct and to be pushed through the hole.





Drilling Contractors Association (DCA-Europe) Bank A & B Offshore Wind Farm

3 Engineering

Methodology

- Each drill required the following operations:
 - Pre-drill and enlarge first 30m of hole and install steel casing/conductor pipe
 - Drill 16" diameter pilot hole from end of conductor pipe to within 50m of exit point
 - Push Hole-Opening to 32" diameter
 - Breakthrough onto seabed
 - Survey to verify suitability of exit position and acceptability of separation from adjacent drilled holes
 - Install cable duct into drilled hole






Drilling Contractors Association (DCA-Europe) Dogger Bank A & B Offshore Wind Farm

3 Engineering







DCA

Drilling Contractors Association (DCA-Europe)

4 Drilling Works


Programme

Throughout Scottish Winter

Casing, Pilot and start Hole-Opening on HDD 1 in 2022


Complete both drills by April 2023

Planned on 12/7 working










Pilot Drilling

- Fairly Conventional with 16.25" HDX drill bit on 9%" mud-motor
- Proceeded well but ROP slower than expected
- Completed largely in line with programme as no problems with wireline etc.
- Steering control well
- Drill fluid returns maintained throughout
- Bit-Wear not excessive









Hole-Opening

- Straight to 32" diameter
- ROP slower than expected due to very high rock strength
- Wear on tools excessive
- Despite challenges, hole-opening completed successfully
- Drill fluid returns maintained throughout hole-opening operations











5 Duct Installation

Duct Installation

- Pipe Pusher :
 - Worked very well
 - Each duct installed in 2-3 hours
 - Generally, 5-25t push throughout
 - Increased to 70t duct limit when pushing through gravels on 1st drill
 - As pusher works in both directions, quick and straightforward to pull back a few metres and push again installation load remained at 35t during second attempt
- Biggest challenge is the lack of such pushers in the market and the risk of lack of availability when required.
- Had to use drill rig to push first duct into final position as a result of the pusher being required elsewhere.






5 Duct Installation

Marine Works

- Minimised by having flanged end connection
- Weather risk reduced by minimising the required extension of the duct beyond the exit point
- Marine works consisted of:
 - Removal of push-head
 - Recovery of gauging pig
 - Fitting bellmouth
 - Securing messenger wire and sealing bellmouth
 - Installing seabed stabilisation
 - Fitting marker buoy
- Spread consisted of Dive/Workboat, Crew-Transfer Vessel operating out of Buckie, 10 km to west








Marine Works - Design

- Initially, Offshore Contractor required 18m long length of duct on seabed ٠
- This exceeded the length of duct that could be safely left on seabed without stabilisation, presenting an adverse ٠ weather delay risk to the duct installation process.
- Agreed to reduce the exposed length to 6 metres which could be left on seabed for several days without stabilisation ٠






5 Duct Installation

C-Tecnics

Marine Works - Construction

13-02-23 09:54:34 Diver 1 J Kyle Location Moray West Depth 12.11M Max Depth 12.98M 00:00:07







6 Summary

Challenges and Solutions

- Winter Landfalls Pipe Installation :
 - Duct pushing
- Duct Pushing :
 - Suitability of Fittings on end of duct potential for slim-flange or similar fittings
 - Availability of pipe-pushers more required
 - Stringing sites need to be considered during project development

